

**City of Sausalito - Muni Lot 2**

**BID SCHEDULE  
BASE BID**

ITEM	BID ITEM DESCRIPTION	QTY	UNIT	BID ITEM UNIT PRICE	BID ITEM TOTAL QUANTITY PRICE
100	MOBILIZATION	1	LS	\$	\$
101	TRAFFIC CONTROL SYSTEM	1	LS	\$	\$
102	WATER POLLUTION CONTROL	1	LS	\$	\$
200	REMOVE CONCRETE CURB AND GUTTER	81	LF	\$	\$
201	SAWCUT EXISTING AC/PCC	359	LF	\$	\$
202	REMOVE CONCRETE SIDEWALK	652	SF	\$	\$
203	REMOVE DROP INLET	1	SF	\$	\$
204	FULL DEPTH ASPHALT REMOVAL	3,469	SF	\$	\$
205	GRIND AC PAVING - 2 INCH	174	SF	\$	\$
206	ABANDON SD LINE	56	LF	\$	\$
207	PROTECT SIGN	2	EA	\$	\$
208	REMOVE WHEELSTOP	18	EA	\$	\$
209	EARTHWORK (EXCAVATION AND REMOVAL)	27	CY	\$	\$
300	CONCRETE CURB AND GUTTER	81	LF	\$	\$
301	CONCRETE VERTICAL CURB	150	LF	\$	\$
302	CONCRETE SIDEWALK	480	SF	\$	\$
303	CONCRETE DRIVEWAY - STANDARD	172	SF	\$	\$
304	CONCRETE WHEELSTOP	19	EA	\$	\$
400	AC PLUG	93	SF	\$	\$
401	FULL DEPTH AC PAVEMENT (MIN. 4 INCH)	95	TON	\$	\$
402	AC PAVING OVERLAY (MIN. 2 INCH)	174	TON	\$	\$
403	CLASS II AGGREGATE BASE (12 INCHES)	135	CY	\$	\$
500	ADJUST TO GRADE (UTILITY VAULTS - TELE/ELEC)	1	EA	\$	\$
600	NEW VEGETATED SWALE	233	SF	\$	\$
700	8" PVC SDR-35 STORM DRAIN PIPE	50	LF	\$	\$
701	8" PERFORATED PVC SDR-35 UNDERDRAIN PIPE	70	LF	\$	\$
702	NEW CATCH BASIN	1	EA	\$	\$
800	STRIPING - 4" WHITE	700	LF	\$	\$
801	STRIPING - 4" BLUE	90	LF	\$	\$
802	STRIPING - RED (CURB)	137	LF	\$	\$
803	STRIPING - PAVEMENT MARKING (ISA SYMBOL)	2	EA	\$	\$
804	PARKING SIGN	2	EA	\$	\$

**TOTAL BASE BID:**

(in words)

**TOTAL BASE BID: \$**

(in numbers)